

MILAM COUNTY R&B #1  
VARIOUS CONCRETE LOW WATER CROSSINGS

LOCATIONS:

- COUNTY ROAD 119, 90'x24'
- COUNTY ROAD 120, 230'x24'
- COUNTY ROAD 147, 75'x24"
- COUNTY ROAD 147, 70'x24'
- COUNTY ROAD 116A, 75'x24'

PLEASE SEE THE PREFERRED BID SPECIFICATIONS BELOW:

All locations shall have a 1' wide x 2' deep toe ditch around the location with ½" rebar at perimeter beams. The slab shall have a ½" rebar spaced at 1' centered and tied. We will require saw cut expansion joints to be cut every 25', and the use of 4,000 psi concrete to be used. The roads shall be barricaded, and closed for 2 days for construction, and 7 days for the proper cure time for the concrete. The existing roadway shall be removed 6" deep, and the top surface of the concrete shall match existing roadway surface and have a broom finish.